



Town of Inuvik

Notice to Bidders

Sanitary Outfall Replacement

Sealed envelopes containing Bids clearly marked "Sanitary Outfall Rehabilitation" and addressed to Town of Inuvik, Town Office, 2 Firth Street, P.O. Box 1160, Inuvik, NWT, X0E 0T0 shall be received at the offices of the Town of Inuvik before **2:00 p.m., local time**, on September 26, 2017.

The Work generally comprises:

- Removal and replacement of existing sanitary sewer Utilidor within Block 3 and Block 15. All removals are Jacket Insulated Steel Pipe on Wood Piles (JIPWP) style, and will be replaced with Jacket Insulated Steel Pipe on Steel Piles (JIPSP).
- Earthwork along the project route as needed for construction purposes and as needed to leave the route properly graded with good drainage and a neat final appearance, and earthworks to improve access roads at sewage lagoon.
- Desludging of existing sewage lagoon and installation of new sewage dumping station.
- The total length of new Utilidor, including road crossing, is approximately 1200 m. New sewer mains are 300mm and 350mm insulated cement lined steel pipe.
- Installation of 120 steel piles.
- Provision of temporary facilities to maintain sewage bypass throughout the project area
- All other work as detailed in the specifications and shown on the Contract Drawings
- Copies of the digital Bid Documents will be made available Monday August 8, 2017, and can be obtained by emailing Stantec at below email address.

Bids should be accompanied by Bid Security in the amount of ten percent (10%) of the Bid Price, payable to the Town of Inuvik. Failure to provide Bid Security will be a factor taken into account when awarding the contract.

Inquiries regarding this Project shall be directed to:

Stantec

10160 – 112 Street
Edmonton, AB T5K 2L6
Attention: Michael Maltais, P.Eng.
Telephone: 780.917-6912
Email: michael.maltais@stantec.com

Town of Inuvik

2 Firth Street
P.O. Box 1160
Inuvik, NWT X0E 0T0
Attention: Senior Administrative Officer